# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT54301

## APPROVED SCHEDULE - B

**No.EE/BTP/BBMP/E-PMT/18/2022-23, Dated: 04-11-2022.**

**Name of Work: Improvements to Roads and Drains at Ramachandrapura Kempanna Layout Roads and Surrounding areas in Ward No. 15 (Kuvempunagara).**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of SURESH UPPALAPATI | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 218.00 | Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. | Cum | 164.7 | Rupees One Hundred Sixty Four and Seventy Paise Only |
| 2 | 32.40 | Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. | Cum | 4918.07 | Rupees Four Thousand Nine Hundred Eighteen and Seven Paise Only |
| 3 | 71.61 | Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 (The cost of steel reinforcement & formwork to be paid separately) | Cum | 5548.9 | Rupees Five Thousand Five Hundred Forty Eight and Ninety Paise Only |
| 4 | 4.54 | Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. | Tonne | 81616.54 | Rupees Eighty One Thousand Six Hundred Sixteen and Fifty Four |
| 5 | 6.00 | Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate | Cum | 5072.14 | Rupees Five Thousand Seventy Two and Fourteen Paise Only |
| 6 | 141.00 | Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with 100 mm thick and Finishing cutting, including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, copmplete. | Sqm | 1667.96 | Rupees One Thousand Six Hundred Sixty Seven and Ninety Six Paise Only |
| 7 | 24.00 | Providing and Fixing pre cast Covering Slab made out of CC 1:2:4 with 230 mm thick and Finishing cutting, including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, copmplete. | Sqm | 4054.8 | Rupees Four Thousand Fifty Four and Eighty Paise Only |
| 8 | 202.74 | Loading and Unloading of Stone Boulder / Stone aggregates / Sand / Kankar / Moorum. (Tipper 14 m3) | Cum | 65.53 | Rupees Sixty Five and Fifty Three Paise Only |
| 9 | 259.50 | Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km | T.Km | 74.81 | Rupees Seventy Four and Eighty One Paise Only |

U. Suresh.

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore- 92**

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು